362

SHIMOGA DIVISION.

ADVERTISEMENTS.

The 21st September 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th October 1887, for constructing a bridge of 4 arches 40′ span over Kumudvati near Shikarpur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes as earnest money, and be superscribed "Tender for constructing a bridge of 4 arches 40 feet span over Kumudvati near Shikarpur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per	Quantity.	Rate.
Earthwork, cutting soft rock	C. Yd.	1,507	
Do sand & shingle and water	"	10,976	
Do excavation, soft rock	"	161	
Do sand and shingle, 1st 6ft.	"	2,863	
Do do 2nd 6ft.	"	1,417	
Do do 3rd 6ft.	"	583	
Baling water, lump sum	..	Rs.	
Coffer dam and shoring	L. S. Rs.	..	
Training bank	..	Rs.	
Stone in surki mortar foundation	C. Ft.	28,566	
Stone in mortar superstructure	"	44,041	
Archwork stone in mortar ring pins	"	1,269	
Do shuting	"	5,922	
Centerings	Each.	4	
Cornicing and coping	C. Ft.	1,416	
Concrete work	C. Ft.	205	
Pointing with mortar	Sq.	169·11	
Drainage pipes	No.	19	
Guard stones	No.	8	
Earth filling foundation and sides with good earth	C. Yd.	7,827	
Do approaches	"	3,627	
Do and cutting side drains ..	"	4,599	
Turfing	Sq.	306·48	
Metalling	C. Yd.	129	
Gravelling	"	708	
Dressing skew backs	L. S. Rs.	Rs.	
Hatting	"	..	

The 21st September 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th October 1887, for the construction of the Sogal Anicut and Channels in

the Honnali Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money and be superscribed "Tender for the construction of the Sogal Anicut and Channels", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for the construction of the Sogal Anicut and Channel, Honnali Taluk.

Items of Work.	Per	Quantities.	Rate.
Earthwork	C. Yd.	77,988	
Do embankment	do	9,956	
Do excavation, soft rock	do	424	
Do do hard do	do	348	
Blasting rock	do	223	
Rough stone in mortar foundation	C. Ft.	3,987	
Stone in mortar foundation	do	14,815	
Do superstructure	do	24,247	
Brick in mortar	do	1,272	
Do	do	10,094	
Plastering with mortar	Sq.	86·07	
Painting do do	do	70·44	
Stone slabs with dog iron	S. Ft.	590	
Do steps, &c.	do	876	
Rough stone work, revetment, &c.	C. Yd.	2,656	
Do sujikat	do	443	
Baling water	L. S.	Rs.	
Ashlar work	C. Ft.	79	
Concrete work, 1st sort	do	982	
Do 2nd sort	do	324	
Covering slabs	S. Ft.	1,150	
Teak wood shutters, &c., complete	No.	3	
Do do	No.	1	
Turfing	Sq.	1,953·75	
Mile stones	No.	6	
Furlong stones	do	42	
Grade stones	do	290	
Index do	do	252	
Iron pipes, 8 " and 9 " diameter	R. Ft.	·27	
Do 6 and 7 do	do	27	
Excavation in hard soil	C. Yd.	393	
Arch work, brick in mortar	C. Ft.	891	
Cornice work	R. Ft.	168	
Centerings	No.	3	
Cut stone slabs	S. Ft.	159	

A. S. NAGAVKAR,
Executive Engineer,